

4-032413

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

20592
API Number: 15-193-20-565-0000

W2 SW /4 SEC. 09, 10, 31 W
1320 feet from S section line
4620 feet from E section line

Operator license# 9482

5/15

Lease: Robben Well # 2

Operator: National Petroleum Reserves

County: Thomas 151.09

Address: 250 N. Rock Road - Suite #130
Wichita, Kansas 67206

Well total depth 4649 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 300 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Poe Servicing, Inc. License# 3152

Address: Oberlin, Kansas 67749

Company to plug at: Hour: A.M. Day: 15 Month: May Year: 2000

Plugging proposal received from: Ted

Company: National Petroleum Reserves, Inc. Phone:

Were: Order 250 sxs 60/40 pozmix - 10% gel - 400# hulls.
Allied Cement Company.

RECEIVED
STATE CORPORATION COMMISSION

MAY 23 2000

Plugging Proposal Received by: Carl Goodrow

CONSERVATION DIVISION
Wichita, Kansas

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:30 A.M. Day: 15 Month: May Year: 2000

Actual plugging report: 8 5/8" set at 300' w/210 sxs cwc. 4 1/2" set at 4507' w/135 sxs.
2 stage at 2600' w/460 sxs cement. Prod Perfs 4270' - 4275'. Squeezed 4 1/2" with 225 sxs
cement blend with 400# hulls mixed in to Max. P.S.I. 500#. Held.
Test-backside-to-300#-- cement at surface. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

INVOICED
DATE 5/25/00
61783

Form CP-2/3

R

STATE: KANSAS **COUNTY:** THOMAS **REISSUE** **9-10S-31W**
FIELD: OTTLEY NORTH C W2 SW
OPER: NATIONAL PET RESERVES 1320 FSL 660 FWL SEC
WELL: 2 ROBBEN **WELL CLASS:** DO **ELEV:** 3029 KB
API: 15-193-20592 **STATUS:** OIL 3024 GR
SPUD: 03/24/92 **COMP:** 04/16/92
DTD: 4649 **LTD:** **FTD:** MISSISSIPPIAN **PBTD:** 4345

LOC: 5 1/2 MI NE OAKLEY, KS

IP: COMP 4/16/92, IPP 24 BO, 2 BWPD, GTY 39 **PROD ZONE-** LANSING-KANSAS CITY
 4270-4275
 NO CORES, FIVE DSTS

LOG TOPS:

ANHYDRITE	2062 967	STARK	4286 -1257
B/ ANHYDRITE	2630 399	B/ KANSAS CITY	4347 -1318
TOPEKA	3817 -788	PAWNEE	4471 -1442
HEEBNER	4034 -1005	JOHNSON ZONE	4507 -1478
TORONTO	4060 -1031	FORT SCOTT	4534 -1505
LANSING	4078 -1049	CHEROKEE	4562 -1533

TD 4649 -1620

LOG TYPES: CNDL, DI, SL;

(OVER)

COPYRIGHT 1993 PETROLEUM INFORMATION CORPORATION

DATE 08/13/93 CARD #00020-KS