

362 R

6 031397

API NUMBER 15- 193-20,522-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE NW, SEC. 10, T 10 S, R 31 W/E

4950 feet from S section line

2970 feet from E section line

Lease Name Robben Well # 1-10

County Thomas 151.13

Well Total Depth 4650 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 250

TECHNICIAN'S PLUGGING REPORT

Operator License # 4629

Operator: Brito Oil Co. Inc.
Name & Address: 200 East First Suite 208
Wichita, Ks. 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A XX

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling License Number 5422

Address Wichita, Ks.

Company to plug at: Hour: AM Day: 14 Month: July Year: 19 90

Plugging proposal received from Harold Maley

(company name) Abercrombie (phone)

were: 8 5/8 set at 250 w/160 sks. Circ hole w/no less than 36 vis mud
w/no loss or gain of fluid, balance plugs w/mud. Order 190 sks 60/40 poz
6% gel 3% cc. Allied Cement Co. Farmer will keep water well.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 3:00AM Day: 14 Month: July Year: 19 90

ACTUAL PLUGGING REPORT Spot plugs w/drill pipe at 2550 w/25 sks

1650 w/100 sks and bulls

300 w/40 sks

40 w/10 sks

Circ 15 sks in rathole w/joint of pipe.

RECEIVED
STATE CORPORATION COMMISSION
8-7-90
AUG - 7 1990
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Anhy 2532-66 Elev. 2948
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE: AUG 15 1990

INV. NO. 28918

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow