

6-22 239 R

6 070927

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 193-20,561-00-00

E/2 E/2 NW, SEC. 15, T 10 S, R 31 W/E
3960 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4629

Lease Name Swart Well # 1-15

Operator: Brito Oil Company, Inc.

County Thomas 152.75

Name & Address 200 E. First

Well Total Depth 4700 feet

Suite 208

Conductor Pipe: Size - feet -

Wichita, Kansas 67202

Surface Casing: Size 8 5/8 feet 289

(Paul F. Brito)

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Blue Goose Drilling License Number 5104

Address Box 1413, Great Bend, Kansas 67530

Company to plug at: Hour: A.M. Day: 22nd Month: June Year: 19 91

Plugging proposal received from Martin Miller

(company name) Blue Goose Drilling (phone) 316-263-8787

were: 8 5/8" 289' S.P. circ. w/170 sxs. cement - 60/40 poz. - 3% gel. - 2% Cal.Cl.

(By Allied) Miss. well-Elv. 3003' - anhy. 2575 - No circulation problems.

Mud cond. 42 vis. - 9.2 weight - water loss 8.9 - Proposal 210 sx. 60/40 poz.

6% gel. - 3% cal. cl. - Spot with drill stem, circulate hole, heavy mud between

all plugs. 25 sx. @2580' - 100 sx. @1700' - 50 sx. @ 330' - 10sx. @ 40' -15sx. rate hole-
10 sx. water well.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:00 A:MDay: 22nd Month: June Year: 19 91

ACTUAL PLUGGING REPORT Brito ordered 210 sx. 60/40 Pozmix - 6% Gel. - 3% Cal Cl. and

1 sx. Flo-Cele. Spotted cement and displaced through drill stem.

1st plug @ 2580' w/25 sx. cement

2nd plug @ 1700' w/100 sx. cement w/1 sx. F.C. 15 sx. Rat Hole (circulate)

3rd plug @ 330' w/50 sx. cement 10 sx. in Water Well

4th plug @ 40' w/10 sx. cement By Allied Cement

RECEIVED STATE CORPORATION COMMISSION 7-3-91 IIII 03 1991

Remarks:

INVOICED

(If additional description is necessary, use BACK of this form.) CONSERVATION DIVISION
Wichita, Kansas

I did not observe this plugging.

DATE 7-18-91

Signed [Signature] (TECHNICIAN)

INV. NO. 32272