

APR 19 1987

API NUMBER 15- 193-20,433-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NE SW, SEC. 15, T. 10 S, R. 31 W

1650 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5063

Lease Name Flipse Well # B-1

Operator: Energy Exp. Inc.

County Thomas 151.78

Name & Address 1002 South Broadway

Well Total Depth 4670' feet

Wichita, Kansas 67211

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 268

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Co. License Number 424

Address 151 North Main #700 Wichita, Kansas 67202

Company to plug at: Hour: PM Day: 19 Month: April Year: 19 87

Plugging proposal received from Marion Burris

(company name) Warrior Drilling (phone)

were: 8 5/8 set @ 268' w/200 sx. Circulate hole w/no less than 36 Vis. mud,

Maintain mud level @ surface, balance plugs w/mud. Order 200 sx. 60/40 Poz. 6% Gel 3% cc.

BJ. TITAN CMT. CO.

Plugging Proposal Received by Carl Goodrow
Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour 10:45 PM Day: 19 Month: April Year: 19 87

ACTUAL PLUGGING REPORT 1st plug @ 2575 w/25 sx. Spot w/D.P.

2nd plug @ 1580' w/100 sx. cmt. and 1sx. Hulls

3rd Plug @ 320' w/40 sx.

4th Plug @ 40' w/10 sx.

15 sx. in Rathole circ. w/Joint of Pipe

10 sx. in Mousehole " " " "

RECEIVED
STATE CORPORATION COMMISSION
5-4-87
MAY 4 1987

Remarks: (If additional description is necessary, use BACK of this

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

observe this plugging.

DATE 5-5-87 In DB mps

Signed Carl Goodrow
Carl Goodrow (TECHNICIAN)

INV. NO. 16757 JUN 11 1987 JUL 08 1987