

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20677-00-00
Spot: NWSENE Sec/Twnshp/Rge: 25-10S-34W
3630 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: MAI Well Number: 1
County: THOMAS Total Vertical Depth: 4735 feet

Operator License No.: 31652
Op Name: NORSTAR PETROLEUM, INC.
Address: 5 INVERNESS DRIVE EAST STE 120
ENGLEWOOD, CO 80112

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 259
Production: Size feet:
Liner: Size feet: 3153.89

Well Type: DH UIC Docket No: Date/Time to Plug: 05/02/2001 12:15 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: BILL WYNN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 05/02/2001 3:00 PM

WitnessType: Plugging Operations Were Not Witnessed
KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 2685' w/25 sxs. Anhydrite 2638' - 2685'.
2nd. Plug at 1650' w/100 sxs. Dakota 1344' - 1644'.
3rd. Plug at 310' w/40 sxs. Surface pipe set to 259'.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

INVOICED

DATE 6-01-01
INV. NO. 2001061878

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 1 2001
06-01-2001
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)