

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20174-00-01
Spot: SENW Sec/Twnshp/Rge: 15-10S-35W
3300 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: MEDFORD FARMS Well Number: 1
County: THOMAS Total Vertical Depth: 5000 feet

Operator License No.: 5386
Op Name: PRODUCTION DRILLING, INC.
Address: PO BOX 680
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 363
Production: Size 4.5 feet: 4600
Liner: Size feet:

8162.50

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/12/2001 1:00 PM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: AVEN Company: ROME CORPORATION DBA WEST Phone: (785) 625-1118

Proposed Plugging Method: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/12/2001 3:30 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 363' w/200 sxs cwc. 4 1/2" set at 4600' cement N/A.
Prod Perf 4430' - 4433'.
Packer stuck in the hole - shot off tubing above packer - fluid dropped.
Pulled tubing. Ran in with perf gun to perforate at critical control areas.
Gun stopped at 1860' - tight casing.
Made shots at 1825'. Holes in casing across cedar hills.
Squeezed 4 1/2" casing with 200 sxs cement blend with 400# hulls to Max. P.S.I. 400#. S.I.P. 300#.
Squeezed 8 5/8" with 50 sxs cement blend to Max. P.S.I. 100#. Held.
Plug complete.

INVOICED
DATE 6-19-01
INV. NO. 2001061964

RECEIVED
KANSAS CORPORATION COMMISSION
06-19-2001
JUN 19 2001
CONSERVATION DIVISION

Remarks:

Plugged through: CSG

District: 04

100

Signed Carl Goodrow
(TECHNICIAN)

DAVE ADAMS
WICHITA, KS 67202

15-10 -35W
C SE NW

#1 MEDFORD FARMS OWWO

site: 12-1/2 S & 8 W OF COLBY, KS
contr: WESTERN KANSAS DRILLING

city: THOMAS
field: WC (4 SW OF DELORES)

API 15-193-20174-A

geol:
fr date 07/15/88 spd date 07/17/88 drig comp card issued 10/26/88 last revised 10/26/88

ELV: 3304 KB LOG
tops.....depth/datum
ANH.....2807 +497
B/ANH.....2836 +468
WAB.....3807 -503
TOP.....3936 -632
OREAD.....4109 -805
HEEB.....4147 -843
LANS.....4189 -885
MUN CR.....4332 -1028
STARK.....4417 -1113
BKC.....4472 -1168
MARM.....4503 -1199
ALT.....4522 -1218
PAW.....4609 -1305

IP status:

OIL, P 28 BOPD, LKC 4430-4433,
CHER UPR.....4661 -1357
CHER LWR.....4699 -1395
JOHNSON ZN.....4742 -1438
MISS.....4846 -1542
LTD OLD.....4998 -1694
RTD OLD.....5000 -1696

NOTE: CORRECTION: 10/26/88 - ORIGINALLY FIRST
REPORTED AS WESTERN KANSAS EXPLORATION &
NEWPORT ENERGY AS OPERATORS; OPERATIONS
TURNED OVER TO DAVE ADAMS
OLD INFO: OPERATOR WAS DONALD C. SLAWSON, 1
STOVER "P", SPD 10/02/78 , 8 5/8" 363/200SX, D & A,
MISS, (CARD ISSUED 11/02/78)
CONTR: DONALD C. SLAWSON
GEOL: RALPH RUWWE (over)

COPYRIGHT 1988
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

DAVE ADAMS
WICHITA, KS 67202

15-10 -35W
C SE NW

#1 MEDFORD FARMS OWWO

NO CORES

DST (1) 4209-4240 (LANS), / 30-60-45-75, REC 40' WM, W/SO ISIP 1302# FSIP 1293# IFP
45# -54# FFP 63# -72#
DST (2) 4257-4282 (LANS), / 30-30-30-30, REC 80' M, NS ISIP 1302# FSIP 1284# IFP 36#
-45# FFP 45# -54#
DST (3) 4325-4365 (LKC), / 30-30-30-30, REC 50' M, NS ISIP 1257# FSIP 1221# IFP 36#
-45# FFP 45# -54#
DST (4) 4359-4395 (LKC), / 30-60-30-60, REC 60' M, NS ISIP 1375# FSIP 1339# IFP 36#
-45# FFP 45# -54#
DST (5) 4415-4445 (LKC), / 30-60-45-75, 60' GIP, REC 170' OIL, 60' VHOCM, 60' SLI OCTM
ISIP 1330# FSIP 1284# IFP 45# -90# FFP 99# -135#
DST (6) 4683-4765 (CHER, JOHNSON ZN), / 30-30-30-30, REC 30' M, NS ISIP 269# FSIP
143# IFP 54# -63# FFP 63# -72#

NEW INFO: FR 07/15/88 , RE-ENTERED 07/17/88 WSH DWN DC CSG: SET 4-1/2" 4600 MICT -
CO, PF (LANS K) 4430-4433, W / 2 SPF, AC 500 GAL (MCA) & 1000 GAL (15% NE), SWB 2.33
BEPH (50% OIL), T & R, POP, P 28 BOPD, 10/18/88