

031485

2-1

72  
72

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 193-20,506 00-00

C NW, SEC. 15, T 10 S, R 35 WXB

3960 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3007

Lease Name Medford Well # B 2

Operator: Western Ks. Exp.

County Thomas 157.91

Name & Address Box 126 2700 Oak St.

Well Total Depth 4859 feet

Hays, Ks. 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 254

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering License Number 5111

Address Great Bend, Ks.

Company to plug at: Hour: PM Day: 1 Month: Feb. Year: 19 91

Plugging proposal received from Charlie Farr

(company name) Western Ks. Exp. (phone)

were: 8 5/8 set at 254 w/170 sks. 4 1/2 set at 4857 w/250 sks. Perfs 4425 - 28.

Order sand and common cement. Pull pipe. Order 250 sks 65/35 poz 10% gel

500 lbs. hulls. Halliburton Cement Co. Hoxie water trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:00 PM Day: 1 Month: Feb. Year: 19 91

ACTUAL PLUGGING REPORT Sand back to 4375 w/5 sks common cement on sand w/bailer.

Shot off at 2640. Laid down 2 joints. Pumped 60 sks cement blend from 2640 to 2320

1000 lb psi. Pipe was stuck in hole. Shot at 1800 pipe was stuck. Shot at 1300. Pipe

was free laid down 4 joints. Pumped cement blend to circulate. Laid down casing.

Tie onto 8 5/8 sq w/total of 245 sks. to max psi 450 lbs. Close in psi 150 lbs.

STATE CORPORATION COMMISSION  
WICHITA, KANSAS

FEB 13 1991  
02-13-1991

Remarks: Plug complete.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did / observe this plugging.

DATE 3-6-91

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 31021

Carl Goodrow