

To: **6 070647**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER ~~15~~ 15-181-20,276-00-00
NW SW SE, SEC. 8, T 10 S, R 41 W/E
731 feet from S section line
2046 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3578

Operator: Medallion Petroleum Inc.
Name & Address 320 S. Boston #200
Tulsa, Ok 74103
Lee Francis

Lease Name Alderman Well # 8-1
County Sherman 173.88
Well Total Depth 5350 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 429

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ O&A ☒ X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Inc. License Number #6033 Tag #614

Address Wichita, Kansas 67202

Company to plug at: Hour: 1:30PM Day: 24 Month: Feb Year: 19 88

Plugging proposal received from Ed McKenna

(company name) Murfin Drilling Inc. (phone) 918-582-4441

were: 8 5/8" - 429' S.P. cwc w/250 sks cement. Common and Light. By Allied.

Narrow well, Elv. 3847'; Anhydrite 3200'; No circulation problems. Mud condition 51 Vis;

9.2 Weight; 6.8 Water Loss. Proposal 210 sks 60/40 Pozmix 6% Gel 3% Ca Cl 1 sk F.C. and

8 5/8" plug. Spot with drill stem, recondition hole. Heavy mud between plugs.

25 sks at 3200'; 100 sks w/1 F.C. at 2400'; 50 sks at 460'; 10 sks at 40'; 15 sks rat hole;

10 sks mouse hole
Plugging Proposal Received by MJS (TECHNICIAN) (Cir)

Plugging Operations attended by Agent?: All ☐ Part ☐ None ☒ X

Operations Completed: Hour: 1:30PM Day: 24 Month: Feb Year: 19 88

ACTUAL PLUGGING REPORT Ordered 210 sks 60/40 Pozmix 6% Gel 2% Ca Cl 1 sk

F.C. and 8 5/8" plug. Circulated hole, spotted with drill stem. Heavy mud between all plugs.

1st plug at 3200' w/25 sks cement; 2nd plug 100 sks w/1 sk F.C. at 2400'; 3rd plug 50 sks at

460'; 4th plug Hulls, plug at 40' w/10 sks cement; 15 sks rat hole, circulate. 10 sks

mouse hole. Circulate.

Remarks: Cemented by B. J. Titan

(If additional description is necessary, use BACK of Wichita, Kansas)

INVOICED
XXX (did not) observe this plugging.

DATE 3-9-88

WTV. NO. 20060

Signed Marion J. Schmidt
(TECHNICIAN)
Marion J. Schmidt

MAR 24 1988