

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-27425-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 6-24S-14E  
3280 feet from S Section Line, 2245 feet from E Section Line  
Lease Name: WINTERSCHIED Well #: 42  
County: WOODSON Total Vertical Depth: 1603 feet

Operator License No.: 8093  
Op Name: HAAS, GARY L. DBA GARY HAAS - OIL  
Address: 600 ARROWHEAD DR  
NEW STRAWN, KS 66839

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	40	0	

52.10

Well Type: OIL DH KCC PRT UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/23/2008 1:00 PM  
Plug Co. License No.: 33557 Plug Co. Name: SKYY DRILLING, LLC  
Proposal Rcvd. from: BEN AHRREL Company: SKY DRILLING, LLC Phone: (816) 531-5922

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED 7 7/8" BORE TO 1603'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' PLUG AT THE KANSAS CITY LIME, AN A CONTINUOUS CEMENT PLUG FROM 200' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/23/2008 4:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

DRILL PIPE WAS RAN INTO THE WELL TO 1600'. THE WELL WAS GELLED FOR BRIDGING PURPOSES. 15 SACKS OF CEMENT WERE PUMED THROUGH THE DRILL PIPE TO 1600'. THE PIPE WAS PULLED TO 800' AND 15 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE DRILL PIPE WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE DRILL PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE DRILL PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED  
KCC DISTRICT #3

DEC 3 2008 CPT

CHANUTE, KS

RECEIVED  
KANSAS CORPORATION CO  
DEC 05 2008  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
DATE 12/8/08  
INV. NO. 2009060792

Remarks:

Plugged through:

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

PRT