

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20850-00-00
Spot: E2NWNE Sec/Twnshp/Rge: 16-30S-8W
4620 feet from S Section Line, 1650 feet from E Section Line
Lease Name: HARTMAN Well #: 1
County: KINGMAN Total Vertical Depth: 4265 feet

Operator License No.: 8740
Op Name: BRAMWELL PETROLEUM, INC.
Address: 15183 SW 25TH AVE
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4266	2375	250 SXS CMT
SURF	8.625	281		275 SXS CMT <u>138.61</u>

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/20/2008 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTIRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: PER KCC RULES

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 10/24/2008 3:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

10/21/2008 SANDED BACK TO 4090' PLACED 4 SXS OF CEMENT ON TOP, RIPPED OFF @ 2375'. PULLED CASING TO 1300' SPOTTED 35 SXS OF CEMENT, PULLED CASING TO 855' SPOTTED 35 SXS OF CEMENT, PULLED CASING TO 364' CIRCULATED 120 SXS OF CEMENT TO SURFACE. 10/22/2008 TOP PLUG FELL BACK 105', 10/24/2008 PLACED 50 SXS IN TOP 105'. OK

Perfs:

Top	Bot	Thru	Comments
4154	4242		

INVOICED
DATE 12-11-08
INV. NO. 2009060821

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 18 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY CEMENT CO. TICKET #2384 60/40 POS MIX WITH 4% GEL

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

