

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20704-00-02
Spot: SWSWSW Sec/Twnshp/Rge: 11-22S-8W
330 feet from S Section Line, 330 feet from W Section Line
Lease Name: JUSTUS Well #: 3-A
County: RENO Total Vertical Depth: 3636 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3626	1511	175 SX
SURF	8.625	260		250 SX

118.17

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/17/2008 5:00 PM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE DBA BRONCO ENERGY SERVICES
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS Phone: (405) 261-0978

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL
Date/Time Plugging Completed: 07/17/2008 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

7/16/2008 SANDED BACK TO 3500' PLACED 4 SXS ON TOP OF SAND, SHOT OFF @ 2474' PULLED 333' CASING PARTED, FISHED TOP OF CASING WITH TOOL FROM KANSAS FISH. 7/17/2008 CAME UP TO 1178' SHOT OFF AND SPOTTED 40 SXS W/CC & 100 LBS OF HULLS, PULLED CASING TO 674' SPOTTED 50 SXS W/CC & 100 LBS OF HULLS, PULLED TO 280' CIRCULATED 70 SXS TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3558	3562		

INVOICED
DATE 12-11-08
INV. NO. 2009060824

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 18 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENT CO. TICKET #32810 CC AND HULLS WERE ADDED ON SITE.

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

PKT