

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-00980-00-01

Spot: SWNESW

Sec/Twnshp/Rge: 2-17S-10W

1641 feet from S Section Line, 3618 feet from E Section Line

Lease Name: PHELAN

Well #: 1

County: ELLSWORTH

Total Vertical Depth: 3282 feet

Operator License No.: 31528

Op Name: KELSO, MIKE OIL, INC.

Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3280		
SURF	8.625	264		

106.67

Well Type: SWD

UIC Docket No: D25342.0

Date/Time to Plug: 10/30/2008 12:30 PM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: MIKES TESTING & SALVAGE

Phone: (620) 562-8088

Proposed
Plugging
Method:

SEE BELOW

Plugging Proposal Received By: DAVE WERTZ

WitnessType: NONE

Date/Time Plugging Completed: 10/30/2008 3:30 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND OPEN HOLE TO 3230' & CAP WITH 5 SX'S CEMENT. PERFORATE @ 1250', 950' & 315'. RUN TUBING TO 1250' & PUMP 35 SX'S CEMENT, PULL TUBING TO 315' & CIRCULATE CEMENT TO SURFACE. CEMENT @ SURFACE ON BACKSIDE OF 5 1/2". TOP OFF AFTER PULLED TUBING. OPEN HOLE 3280-3478.

Perfs:

Top	Bot	Thru	Comments
3280	3478		

INVOICED
DATE 12-11-08
INV. NO. 2009060825

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 18 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS TICKET #5514. COPELAND CEMENT TICKET #353999

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

PS