

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20018-00-00  
KCC Pkt per CP 2/3  
Spot: EZE2SW Sec/Twnshp/Rge: 2-17S-10W  
1320 feet from S Section Line, 1980 feet from W Section Line  
Lease Name: PHELAN Well #: 2  
County: ELLSWORTH Total Vertical Depth: 3292 feet

Operator License No.: 31528  
Op Name: KELSO, MIKE OIL, INC.  
Address: PO BOX 467  
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3290		100 SX
SURF	8.625	257		

106.99

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/30/2008 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DAVE WERTZ Witness Type: NONE  
Date/Time Plugging Completed: 10/30/2008 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND OPEN HOLE TO 3240' & CAP WITH 5 SX'S CEMENT, PERFORATE @1250', 950' & 310'. RUN TUBING TO 1250' & PUMPED 35 SX'S, PULL TUBING TO 950' & PUMP 35 SK'S, PULL TUBING TO 310' & CIRCULATE CEMENT TO SURFACE. PULL TUBING & TOP OFF. OPEN HOLE 3290'-92'.

Perfs:

Top	Bot	Thru	Comments
3290	3292		

**INVOICED**  
DATE 12-11-08  
INV. NO. 2009060825

RECEIVED  
KANSAS CORPORATION COMMISSION  
**NOV 18 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL LOG TECH TICKET #5515. COPELAND TICKET #353998

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

Pkt