

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-22536-00-00  
Spot: NWNENE Sec/Twnshp/Rge: 3-19S-10W  
330 feet from N Section Line, 1010 feet from E Section Line  
Lease Name: HABIGER ET AL Well #: 1-3  
County: RICE Total Vertical Depth: 3388 feet

Operator License No.: 3882  
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN  
Address: 1560 BROADWAY STE 2100  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3373	2240	25/125 SX CMT.
SURF	8.625	332		175 SX CMT. <u>110.11</u>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/11/2008 5:00 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: KELLY BRANUM Company: SAMUEL GARY & ASSOCIATES Phone: \_\_\_\_\_

Proposed Plugging Method: PER KCC RULES

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/11/2008 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED TO 3197' PLACED 5 SXS OF CEMENT WITH BALER, PULLED CASING TO 1210' SPOTTED 35 SXS CEMENT & 100LBS OF HULLS, PULLED CASING TO 866' SPOTTED 35 SXS OF CEMENT AND 100 LBS OF HULLS, PULLED CASING TO 396' CIRCULATED 145 SXS OF CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3278	3286		
3271	3278		
3263	3266		

RECEIVED  
KANSAS CORPORATION COMMISSION  
NOV 18 2008  
CONSERVATION DIVISION  
WICHITA, KS

**INVOICED**

DATE 12-11-08  
INV. NO. 2009060826

Remarks: QUALITY WELL SERVICE TICKET #1859 60/40 4% GEL = POS MIX

Plugged through: CSG

District: 02

Signed [Signature] (TECHNICIAN)

*PKT*