

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21136-00-01  
Spot: SENE Sec/Twnshp/Rge: 36-32S-9W  
3300 feet from S Section Line, 660 feet from E Section Line  
Lease Name: KINNARD A Well #: 1  
County: HARPER Total Vertical Depth: 3980 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3807	1850	350 SX
SURF	8.625	264		200 SX

129.35

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/25/2008 7:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: CARL W. DURR Company: WOOLSEY OPERATING CO Phone: (620) 886-5606

Proposed Plugging Method: AS PER KCC RECOMMENDATION.

Plugging Proposal Received By: B. J. HOPE WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/26/2008 3:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

8/25/2008 SANDED BACK TO 3370' PLACED 4 SXS OF CEMENT ON TOP. RIPPED OFF @ 1850' PULLED UP TO 1280' SPOTTED 35 SXS OF CEMENT, PULLED UP 857' SPOTTED 35 SXS OF CEMENT, PULLED UP TO 349' AND CIRCULATED 90 SXS OF CEMENT TO SURFACE. 8/26/2008 FELL BACK 71' ADDED 20 SXS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3648	3654		
3417	3721		
2778	2782		

**INVOICED**  
DATE 12-11-08  
INV. NO. 2009060827

RECEIVED  
KANSAS CORPORATION COMMISSION

NOV 18 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY CEMENTING CO. TICKET #2217 60/40/4% GEL POS MIX

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

PKT