

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25256-00-00
Spot: NESWNW Sec/Twnshp/Rge: 1-18S-12W
1710 feet from N Section Line, 925 feet from W Section Line
Lease Name: LIEBLE ET AL Well #: 2-1
County: BARTON Total Vertical Depth: 3525 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1560 BROADWAY STE 2100
DENVER, CO 80202

String Size Depth (ft) Pulled (ft) Comments
SURF 8.625 369

114.56

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/03/2008 8:00 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: KIRBY Company: SAMUEL GARY JR. & ASSOCIATES Phone: (303) 831-4673

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE
Date/Time Plugging Completed: 10/03/2008 2:30 PM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st. Plug at 3350' w/25 sxs.
2nd. Plug at 740' w/25 sxs.
3rd. Plug at 420' w/100 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

INVOICED
DATE 12-11-08
INV. NO. 2009060816

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Ed Schumacher

(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

CM plug

NOV 17 2008 Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

NOV 13 2008