

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21329-00-01
Spot: NWSWSE Sec/Twnshp/Rge: 16-25S-9W
1006 feet from S Section Line, 1989 feet from E Section Line
Lease Name: ROYCE A Well #: 2
County: RENO Total Vertical Depth: 4140 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4139	2390	
SURF	8.625	228		
T1	2.375	3750		134.55

Well Type: SWD *FOR RECEIPT PER UIC* UIC Docket No: E28102.1 Date/Time to Plug:
Plug Co. License No.: *RECEIPT PER UIC* Plug Co. Name:
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS Phone: (620) 546-4801

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 06/09/2008 1:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

6/6/2008 SET CIBP@3800 PLACED 2 SXS OF CEMENT ON TOP, PULLED CASING TO 1463' SPOTTED 35 SXS OF CEMENT, PULLED CASING TO 777' SPOTTED 35 SXS OF CEMENT, PULLED CASING TO 280' CIRCULATED 100 SXS TO SURFACE. 6-9-2008 RAN IN WITH 2 3/8 TUBING TO 200' AND CIRCULATED 100 SXS OF CEMENT. 6-10-2008 CELLER FLOOR COVERED WITH CEMENT.

Perfs:

INVOICED
DATE 12-11-08
INV. NO. 2009060824

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 18 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: BASIC ENERTY TICKET #20994 60-40-4% GEL, POS MIX

Plugged through: CSG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

PKT