

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-193-20506-00-00

LEASE NAME Medford

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER "B" #2

3960 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 15 TWP. 10 RGE. 35 (E) or (W)

COUNTY Thomas

Date Well Completed _____

Plugging Commenced 1-25-91

Plugging Completed 2-1-91

LEASE OPERATOR Western Kansas Drilling, Inc.

ADDRESS Box 126, Hays, Kansas 67601

PHONE# 013-628-2296- OPERATORS LICENSE NO. 4083

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 25, 1991 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. ?

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	250'	None
				4-1/2"	4537'	1,358.74'

MAR 21 1991
03-21-1991
CONSERVATION DIVISION
Wichita Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 4340' and 4 sacks cement. Shot casing at 3828', 3499', 3213', 3008', 2744', 2646', 1840' and 1301'. Pulled 38 joints of 4-1/2" casing. Halliburton plugged well with 300# hulls and 40 sacks 60/40 pozmix cement with 6% gel at 2586', 300# hulls and 40 sacks cement at 1141' and 125 sacks 65/35 pozmix cement with 6% gel down the 8-5/8"

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Western Kansas Drilling, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 20th day of March, 1991

Iona M. Leatherman
Notary Public

My Commission Expires:

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-91