


15-193-00049-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Thomas County. Sec. 29 Twp. 10 Rge. (E) 35 (W)
Location as "NE/CNWxSWx" or footage from lines SW SW NE
Lease Owner D.R. Lauck Oil Company, Inc.
Lease Name Stover Well No. 1
Office Address 301 So. Broadway Wichita 2 Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed June 20 19 52
Application for plugging filed June 20 19 52
Application for plugging approved June 20 19 52
Plugging commenced June 20 19 52
Plugging completed June 20 19 52
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 4995 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale & sand	water	0	280	8 5/8	280	cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

mud 4995 - 270
plug 270 - 265
cement 265 - 235
mud 235 - 40
cement 40 - bottom of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D. R. Lauck Oil Company, Inc.
Address Wichita Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James F. Ralstin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *James F. Ralstin*
Wichita Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of June, 19 52



Elizabeth Gay
Notary Public.

PLUGGING
FILE SEC 29 T. 10 R. 35
BOOK PAGE 26 LINE 28

RECEIVED
STATE CORPORATION COMMISSION
JUL - 1 1952
07-01-1952
CONSERVATION DIVISION
Wichita, Kansas

15-193-00049-00-00

D. R. Lauck Oil Company, Inc.,
North American Car Corporation;

Stover #1 SW SW NE Sec. 29-10-35W
Thomas County, Kansas

Commenced: May 31, 1952
Completed: June 20, 1952

D & A

Elevation: 3324 DF 3326 KB

280' 8 5/8" casing cemented with 150 sacks

Surface soil & shale	60
sand	80
shale	160
sand	190
shale & shells	1140
chalk lime	1210
black shale & shells	1300
shale & shells	1520
sand & shale	1705
shale & shells	2160
red bed & shells	2250
salt & shale	2350
shale & lime	2805
lime	2830
shale & lime	3120
lime & shale	3280
shale & lime	3395
shale & sandy lime	3455
shale & lime	3567
lime	3630
lime & shale	3755
lime	4850
cherty lime	4865
lime	4975

<u>Tops</u>	
Heebner	4142
Lansing	4184
Base Kansas City	4528
Marmaton	4576
Cherokee	4707
Predemoine	4814
sand	4887
Mississippi Chert	4892
Mississippi Lime	4896
Rotary T.D	4995

DST 4264-4298 open 45 min.
rec. 900' saltwater
BHP 1170, FFP 380 15 min.

I hereby certify that the above is a true and correct log of the Stover #1 well, to the best of my knowledge and belief.

PLUGGING
FILE SEC 29 T 10 R 35W
BOOK PAGE 26 LINE 25

James F. Ralstin
James F. Ralstin

Subscribed and sworn to before me this 24th day of June, 1952.

Elizabeth Gay
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
My commission expires Sept. 14, 1955.
07-01-1952
CONSERVATION DIVISION
Wichita, Kansas