

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM

(File One Copy)

API NUMBER 15-193-2041 ^{20, 401-00-00} (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR JAY BOY OIL, INC. OPERATORS LICENSE NO. 4569

ADDRESS 8400 Killarney, Wichita, KS. 67206 PHONE # (316) 263-5781

LEASE (FARM) Krug WELL NO. 2 WELL LOCATION SE SE NE COUNTY Thomas

SEC. 27 TWP. 105 RGE. 32 (~~XXX~~(W) TOTAL DEPTH LTD 4673 RTD 4677 PLUG BACK TD --

Check One:

OIL WELL GAS WELL D & A X SWD or INJ WELL DOCKET NO.

8 5/8"
SURFACE CASING SIZE 296' SET AT 304' CEMENTED WITH 200 SACKS

N/A CASING SIZE SET AT CEMENTED WITH SACKS

PERFORATED AT N/A

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL (Anhy) 20 sx; (Dakota) 100 sx w/1 sk Flocele;
(SC+40'), 40 sx; 40' - 10 sx w/ sol. bridge, Rathole 15 sx.

50-50 Pozmix 6% gel

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes
(If not, explain) Filed w/ACO-1

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 1:00 P.M. April 1, 1986

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

C.K. Morrison

PHONE # (316) 263-5781

ADDRESS Jay Boy Oil, Inc. 8400 Killarney, Wichita, KS. 67206 **RECEIVED**
STATE CORPORATION COMMISSION

PLUGGING CONTRACTOR Halliburton Services LICENSE NO. MAY 6 - 1986

ADDRESS Box 47, Oberlin, KS. 67749 PHONE # (913) 475-2088 05-06-1986
CONSERVATION DIVISION
Wichita, Kansas

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: C.K. Morrison
(Operator or Agent)

DATE: May 6, 1986

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

PLUGGED

Starting Date March 20, 1986

API Number 15- 193-20, 401-00-00

OPERATOR: License # 4569
Name: Jay Boy Oil, Inc.
Address: 8400 Killarney
City/State/Zip: Wichita, KS. 67206
Contact Person: C. K. Morrison
Phone: 316-263-5781

SE SE NE Sec. 27 Twp. 10 S, Rg. 32
2970 Ft. from South Line of Section
330 Ft. from East Line of Section

CONTRACTOR: License # 5381
Name: Big Springs Drilling, Inc.
City/State: Wichita, Kansas 67208

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 330 feet
County: Thomas

Well Drilled For: Oil SWD Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Lease Name: Krug Well #: 2
Ground surface elevation 3040 feet MSL
Domestic well within 330 feet: yes X no

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Municipal well within one mile: yes X no
Depth to bottom of fresh water 250'
Depth to bottom of usable water 1850'

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 3-19-86 Signature of Operator or Agent Title: President

Surface pipe by Alternate: 1 2 X
Surface pipe planned to be set 300' NO
Conductor pipe required
Projected Total Depth 4650 feet
Formation: Mississippian

For KCC Use:
Conductor Pipe Required 8-19-86 feet; Minimum Surface Pipe Required 300 feet per Alt. 6125
This Authorization Expires

Terry Austin 3-21-86
Big Springs

Water well being drilled

SE SE NE Sec. 27 Twp. 10 S, Rg. 32 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays). KCC District #6-Hays (913)628-1200. Disc w/ Dave Wann 3/14/86

1st plug @ (Anhy) ±2575 feet depth with 20 sxs of 50-50 Poz. 6% gel 3% CC
2nd plug @ (Dakota) ±1850 feet depth with 100 sxs of a/a +1skcelloflakes
3rd plug @ (SC+40') ±340 feet depth with 40 sxs of a/a
4th plug @ 40 feet depth with 10 sxs of a/a w/solid bridge
5th plug @ feet depth with sxs of
(2) Rathole with 15 sxs (b) Mousehole with 10 sxs

NOTE: Agreement between operator and district office on plug placement and the amount of cement to be used is necessary prior to plugging. In Addition: Call district office after well is either plugged or production casing is cemented in. (Call 7 a.m. to 5 p.m. workdays)

District office use only:

API #15-
Surface casing of feet set with sxs at
Alternate 1 or 2 surface pipe was used.
Alternate 2 cementing was completed @ ft. depth with
Hole plugged 19 agent

RECEIVED
KCC DISTRICT #6
MAY 21 1986
JOHN DIST #6
HAYS, KS

RECEIVED
STATE CORPORATION COMMISSION
07-11-1986
JUL 11 1986

CONSERVATION DIVISION
Wichita, Kansas