

Amended

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

007-02649-00-00

API # 15 - unable to find identifier # (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 9-2-1956

Well Operator: Apollo Energies Inc KCC License #: 30481
(Owner / Company Name) (Operator's)

Address: 10378 N. 281 Hwy City: Pratt

State: KS Zip Code: 67124 Contact Phone: (620) 672 - 9001

Lease: Williams Well #: 1 Sec. 3 Twp. 33 S. R. 11 East West

C - S/2 - N/2 Spot Location / QQQQ County: Barber

KCC PPT 1890 1980 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2640 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 278 Cemented with: 250 Sacks

Production Casing Size: 5 1/2" Set at: 4590 Cemented with: 125 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4465-4490

Elevation: 1526 (G.L. / K.B.) T.D.: 4590 PBDT: 4555 Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): As Per KCC recommendations

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 02 2008

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Unable to find ACO-1 Copy CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Jim Byers - Kevin Fischer

Apollo Energies, Inc Phone: (620) 672 - 9001

Address: 10378 N. 281 Hwy City / State: Pratt KS 67124

Plugging Contractor: Quality Well Service KCC License #: 31925
(Company Name) (Contractor's)

Address: 401 W Main Lyons, KS Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): ASAP

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 12/1/08 Authorized Operator / Agent: _____
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202


COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- HULF OIL CORPORATION
Farm- C. D. Williams No. 1

SEC. 3 T. 33 R. 11W
C S/2 N/2
1980' S. N. L. & 2640'
E. W. L.
County Barber KANSAS

Total Depth. 4590'
Comm. 9-2-56 Comp. 9-20-56
Shot or Treated.
Contractor.
Issued. 11-24-56



Elevation. 1522' DP

Production. 8,200,000 CF/GPD

Figures indicate Bottom of Formations.

clay	40
red rock	280
red bed	690
shale	800
shale & lime	1075
shale	1153
shale & shells	1565
lime	1795
shale & lime	3042
lime	3255
shale	3735
sand & shale	3757
shale	3797
lime	4392
lime & shale	4418
lime	4480
Cherty lime	4493
lime	4502
Cherty lime	4590
Total Depth	

SAND RECORD
Mississippi Chert
(4464-4490')

Perf. w/swing jet 4464-90'.
Acidized w/1000 gals. mud acid.
sand fraced w/30,000 gals.
crude 45,000# sand & 1500#
Adomite.

GEOLOGICAL TOPS	
Heebner	3612
Douglas sand	3737
Brown lime	3799
Lansing-Kansas City	3803
Mississippi chert	4462
Mississippi lime	4513

K. G. S. LIBRARY

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 02 2008

CONSERVATION DIVISION
WICHITA, KS