



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 20 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

D2-20-1969

15-181-20005-00-00

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Swede Holaday of Mack Oil Company, has this date requested permission to plug the following described well:

Mr. Holaday guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name: Darnauer Well No. 1

Location: CNW-NW Sec. 3 Twp. 10 Rge. (E)(W) 40

County: Sherman Total Depth 5240' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Holaday was instructed to plug the well as follows:

360'--8 5/8" Surface casing, cement circulated with 350 Sx.  
Dakota section from 1952 to 2054'.

Circulate hole with heavy mud. Pull DP to 2075 and displace 100 Sx.  
cement thru DP. Pull DP to 375' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*M. J. Nichols*