

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 3 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 02-03-1969

15-181-20004-00-00

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Swede Holaday of Mack Oil Company, has this
 date requested permission to plug the following described well:

Mr. Holaday guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name: Mary Browne Well No. 1

Location: CNE-NE Sec. 10 Twp. 10 Rge. (E)(W) 41

County: Sherman Total Depth 5330 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Holaday was instructed to plug the well as follows:

376'--8 5/8" Surface casing, cement circulated with 300 Sx.
Dakota section from 2132' to 2310'.

Circulate hole with heavy mud. Pull DP to 2350' and displace 120 Sx.
cement thru DP. Pull DP to 400' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent