



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 2 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ed. Weiler of Shields Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Mallonee-Mahoney, Incorporated,

Complete Address: 925 Sutton Place, Wichita, Kansas.

Lease Name: Broeckelman Well No. 1

Location: CSW-SW Sec. 6 Twp. 10 Rge. (E)(W) 30

County: Sheridan Total Depth 4655' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Weiler was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1375'.

Circulate hole with heavy mud. Pull DP to 1600' and displace 100 Sx.  
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP. Pull  
DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of  
cellar.

Very truly yours,

A. L. D. Nichols  
Conservation Division Agent