

15-179-20261-00-00

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1970

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ed Weiler of Shields Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Incorporated.

Complete Address: Shields Building, Russell, Kansas.

Lease Name: Baalman Well No. A-1

Location: NW-NW-SW Sec. 1 Twp. 10 Rge. (E)(W) 30

County: Sheridan Total Depth 4266' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Weiler was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 1325'.

Circulate hole with heavy mud. Pull DP to 1550' and displace 100 Sx.

cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.

Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

H. G. Nichols
Conservation Division Agent