



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 10 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. D. J. Iannitti of Woodman & Iannitti Drlg., Co. has this date requested permission to plug the following described well:

Mr. Iannitti guarantees payment of the plugging fee.

Operator's full Name: Woodman & Iannitti Drilling Company,

Complete Address: 706 Union National Building, Wichita, Kansas.

Lease Name: Chapman Well No. 1

Location: SW-SW-NW Sec. 36 Twp. 10 Rge. (E)(W) 29

County: Sheridan Total Depth 4121' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Iannitti was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated with 160 Sx.

Circulate hole with heavy mud. Pull DP to 1325' and displace 100 Sx. cement thru DP. Pull DP to 225' and displace 25 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

A. L. Nichols  
Conservation Division Agent