

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 29 1967

CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Jim Woods of Sun Oil Company, has this

date requested permission to plug the following described well:

Mr. Woods guarantees payment of the plugging fee.

Operator's full Name: Sun Oil Company,

Complete Address: Box #3383, Tulsa, Oklahoma.

Lease Name: Project Well No. 3

Location: SE/4 of Sec. 31 Twp. 10 Rge. (E)(W) 29

County Sheridan Total Depth 2029' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Woods was instructed to plug the well as follows:

319'--7" OD Surface pipe, cement circulated with 120 Sx. (6 1/4" Hole).
Dakota section from 1245' to 1550'.

Circulate hole with heavy mud. Pull DP to 1575' and displace 85 Sx.
cement thru DP. Pull DP to 330' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' and with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

Very truly yours,

W. L. Nichols
 Conservation Division Agent