



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 27 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Niernberger of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Niernberger guarantees payment of the plugging fee.

Operator's full Name: F & M Oil Company,

Complete Address: 603 Union Center, Wichita, Kansas.

Lease Name: Meier Well No. 1

Location: SW-SE Sec. 35 Twp. 10 Rge. (E)(W) 29

County: Sheridan Total Depth 4155 --Oil Well


Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Niernberger was instructed to plug the well as follows:

171'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1200'.

Circulate hole with heavy mud. Pull DP to 1430' and displace 110 Cu. Ft. cement thru DP. Pull DP to 200' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

  
Conservation Division Agent