

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 2 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Richardson of Slawson Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Richardson guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Spiers Well No. A-1

Location: SE-SE-NW Sec. 29 Twp. 10 Rge. (E)(W) 32

County: Thomas Total Depth 4680' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Richardson was instructed to plug the well as follows:

289'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1450'.

Circulate hole with heavy mud. Pull DP to 1675' and displace 110 Cu. Ft. cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

*M. L. Nichols*  
Conservation Division Agent