

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 27 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ronnie Parks of Gabbert-Jones, Inc., has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Comet Petroleum Corporation,

Complete Address: 200 West Douglas, Suite 500, Wichita, Kansas.

Lease Name: Broeckelman Well No. 1

Location: CNE-SW Sec. 6 Twp. 10 Rge. (E)(W) 30

County: Sheridan Total Depth 4659' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Parks was instructed to plug the well as follows:

238'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1325'.

Circulate hole with heavy mud. Pull DP to 1600' and displace 100 Sx.  
cement thru DP. Pull DP to 310' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent