

11-14

4-020032

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,616-00-00

SE NW NE /4 SEC. 14, 10 S, 31 W
4290 feet from S section line
1650 feet from E section line

Operator license# 6111
Operator: N-B Company, Inc.
Address: P.O. Box 506
Russell, KS 67665-0506

Lease: GMT-Beckman Well # E-1
County: Thomas
Well total depth 4599 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 255 feet

149.46

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: P.O. Box 506, Russell KS 67665-0506

Company to plug at: Hour: Day: 14 Month: November Year: 1993

Plugging proposal received from: Tom Alm

Company: Emphasis Oil Operations Phone: 913/483-3518

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2550 feet with	25 sacks	Rat hole:	15 sacks
2nd plug @ 1650 feet with	100 sacks	Mouse hole:	10 sacks
3rd plug @ 300 feet with	40 sacks		
4th plug @ 40 feet with	10 sacks		

Plugging Proposal Received by: Ken Kuhn

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 15:00, Day: 14, Month: November, Year: 1993

Actual plugging report: Hole reported plugged as above.

Order 200 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Allied Cementing performed the cementing

Condition of casing(in hole): GOOD X BAD Any plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: 2953 GL

I did [X] did not [] observe the plugging.

INVOICED
DATE 11-19-93
INV. NO. 39261

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1993
CONSERVATION DIVISION
Wichita, Kansas
Form CP-2/3