

4- 062560

12-26

228
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,584-00-00

C SW NE /4 SEC. 14, 10 S, 31 W
3300 feet from S section line
1980 feet from E section line

Operator license# 06111

Lease Beckman A well # 2

Operator: N-B Company, Inc.

County Thomas

Address: Box #506
Russell, Kansas 67665-0506
Kyle B. Branum 913-483-5345

Well total depth 4550 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 253 feet

147.87

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 08241

Address: Russell, Kansas 67665

Company to plug at: Hour: 2:45P.M. Day: 23 Month: December Year: 91

Plugging proposal received from: Tom Alan

Company: Emphasis Oil Operations Phone: 913-483-5345

Were: Order 200 sks. of 60/40 posmix - 6% gel. and 1 sk. flocele.

Plugging Proposal Received by: Gilbert G. Scheck

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 3:30P.M., Day: 26, Month: December, Year: 91

Actual plugging report:

- 1st. plug @ 1612' w/ 25 sks. - Elev. 2912'.
- 2nd. plug @ 1300' w/100 sks. - 1 sk. flocele.
- 3rd. plug @ 300' w/ 40 sks.
- 4th. plug @ 40' w/ 10 sks. - Anhy. 2490' - 2523'.

RECEIVED
KANSAS CORPORATION COMMISS

JAN 6 1992

15 sks. in Rathole.
10 sks. in Mousehole.

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Condition of casing(in hole):GOOD X BAD Anhy. plug: YES 2490' NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 2912' GL

I did[] / did not[X] observe the plugging.

Gilbert G. Scheck

(agent)

Form CP-2/3

INVOICED

DATE 1-10-92
INV. NO. 34298