

6-090472

11-27

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-193-20,579-0000

SE NW NE /4 SEC. 19, 10 S, 31 W  
~~0904190~~ feet from S section line  
1650 feet from E section line

Operator license# 5135

Lease Baalman "B" well # 1

Operator: John O. Farmer, Inc.

County Thomas

Address: P.O. Box 352  
Russell, Kansas 67665

Well total depth 3500 feet 113.75  
Conductor Pipe:        inch @        feet  
Surface pipe 8 5/8 Inch @ 302 feet

Aband. oil well       , Gas well       , Input well       , SWD       , D & A X

Plugging contractor: Shields Drilling Company, Inc. License# 5655

Address: Russell, Kansas

Company to plug at: Hour: AM Day: 26 Month: November Year: 1991

Plugging proposal received from: Burton Beery

Company: Shields Drilling Company, Inc. phone:                     

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 2590 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1720 feet " 100 " Mousehole: 10 sacks

3rd plug @ 350 feet " 40 "

4th plug @ 40 feet " wiper plug & 10 sx.

5th plug @        feet "

Plugging Proposal Received by: Ed Schumacher P.I.R.T. III  
Plugging operations attended by agent? All[        ], Part[        ], None

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 09 1991

Completed: Hour: 2:30 PM, Day: 27, Month: November, Year: 1991

Actual plugging report: Hole reported plugged as above.  
Order 200sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 3020 GL, Anhydrite depth: 2570 - 2605 feet

Did Not penetrate Arbuckle, cemented by Halliburton Cementing Company

I did[        ] / did not[ X ] observe the plugging.

Ed Schumacher

DATE 12-11-91  
INV. NO. 34112

*Gill G. Schell*

Ed Schumacher P.I.R.T. III  
(agent)