

2-7-88 115 R
API NUMBER 15- 193-20,457-00-00

6 020449

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE SE , SEC. 33 , T 10 S, R 31 W/E
990 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 7802

Operator: Rider Oil and Gas
Name & Address: 225 N. Market Suite 330
Wichita, Kansas 67202
316-264-8200

Lease Name Mifler Well # 1
County Thomas 151.78
Well Total Depth 4670 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 269.73

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Oper License Number 8241

Address Russell, Ks.

Company to plug at: Hour: 4:00PM Day: 7 Month: Feb Year: 19 88

Plugging proposal received from _____

(company name) Emphasis Oil Oper (phone) 483-3518

were: Order 200 sks 60/40 Poz 6% Gel 3% Cal Cl 1 sk F.C. and 8 5/8" plug.
Spot with drill pipe with no less than 36 vis mud between all plugs with good
circulation and no fluid loss.

Plugging Proposal Received by Gil Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:00PM Day: 7 Month: Feb Year: 19 88

ACTUAL PLUGGING REPORT Cir.

1st plug at 2570' w/25 sks
2nd plug at 1700' w/100 sks F.C. 1 sk in all
3rd plug at 280' w/40 sks
4th plug at 40' w/10 sks w/wiper
15 sks in rat hole 10 sks in mouse hole.

Remarks: Halliburton Cement Co.

additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Gil Balthazor (TECHNICIAN)

DATE 2-29-88 2-23-88

INV. NO. 99942