

6 030366

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-193-20,335-0000  
NE, SEC. 34, T 10 S, R 31 WE  
3630 feet from N/S section line  
330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5063

Lease Name J.R Well # 1  
County THOMAS 149.50

Operator: ENERGY EXPLORATION INC.  
Name & Address 1002 SOUTH BROADWAY  
WICHITA, KANSAS  
67211

Well Total Depth 4600 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 298

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor ABERCROMBIE DRUG. License Number 5422

Address 801 UNION CENTER WICHITA KANSAS 67202

Company to plug at: Hour: PM Day: 15 Month: 12 Year: 19 84

Plugging proposal received from WALLY TOWNS

(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: ORDER 200 SX. 50/5002 6" GEL 3" - 1" WIPER PLUG 8 5/8"  
SPOT WITH DR. WITH HEAVY MUD BETWEEN PLUGS NO FLUID LOSS

RECEIVED  
STATE CORPORATION COMMISSION

1-2-85  
Plugging Proposal Received by Carl Goodrow  
JAN 02 1985 (TECHNICIAN)

Plugging Operations attended by Agent?: A CONSERVATION DIVISION Part \_\_\_\_\_ None X  
Wichita, Kansas

Operations Completed: Hour: 3:PM Day: 15 Month: 12 Year: 19 84

ACTUAL PLUGGING REPORT RAND.P. TO 2500' DISPLACED WITH 25 SX. CEMENT  
PULLED D.P. TO 1550' DISPLACED WITH 100 SX. CEMENT PULLED D.P.  
300' DISPLACED WITH 40 SX. CEMENT PULLED D.P. SET PLUG WITH HULLS  
AND 10 SX. CEMENT TO BOTTOM CELLAR - CIRCULATED 15 SX CEMENT IN  
RATHOLE AND 10 SX. CEMENT IN MOUSE HOLE.

SUN CEMENT CO. ELEV. 2935 KB ANHY 2485-2516

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(did, did not) observe this plugging.

DATE 1-14-85

Signed Carl Goodrow  
(TECHNICIAN)

INV. NO. 6410

Jan 28 1984  
10