

12-11

90.8

6- 050097

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,605-0000

N2 N2 NW /4 SEC. 7, 10 S, 32 W
4950 feet from S section line
3960 feet from E section line

Operator license# 5285 Lease Peck A well # 1

Operator: Dane G. Hansen Trust County Thomas

Address: P. O. Box 187 Well total depth 4465 feet ^{145.11}
Logan, Kansas Conductor Pipe: ___ inch @ ___ feet
Surface pipe 8 5/8 Inch @ 260 feet

Aband. oil well ____, Gas well ____, Input well ____, SWD ____, D & A X

Plugging contractor: Chief Drilling License# 5886

Address: Wichita, Kansas

Company to plug at: Hour: PM Day: 11 Month: December Year: 1992

Plugging proposal received from: Harold Dinkle

Company: Chief Drilling phone: _____

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2630 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1785 feet " 100 " Mousehole: 10 sacks

3rd plug @ 310 feet " 40 "

4th plug @ 40 feet " wiper plug & 10sx

Plugging Proposal Received by: Bruce D. Basye

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 1:30 PM, Day: 11, Month: December, Year: 1992

Actual plugging report: Hole reported plugged as above.
Order 195 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 3085 GL, Anhydrite depth: 2613 - 2640 feet

Did penetrate Arbuckle, cemented by Allied

I did[] / did not[X] observe the plugging.

Bruce Basye
Bruce D. Basye Geologist
(agent)
STATE CORPORATION COMMISSION
RECEIVED
DEC 23 1992
Form CP-2/3
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 1-14-92

INVOICE NO. 37200