

R

6 010617

5-27-88

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 193-20,462-0000  
NW NW NW, SEC. 7, T 10 S, R 32 W/  
4950 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8541, Inc.  
Operator: Petex Inc.  
Name & Address Rt. 2, Box 553  
Rogersville, Mo.

Lease Name Peck Well # 1  
County Thomas 151.45  
Well Total Depth 4660 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8" feet 290'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Blue Goose Drilling License Number 5104

Address Great Bend, Kansas

Company to plug at: Hour: \_\_\_\_\_ Day: 27 Month: 5 Year: 19 88

Plugging proposal received from M. Miller

(company name) 2257 Blue Goose (phone) \_\_\_\_\_

were: Order 205 sx cement 60/40 pozmix- 6 % gel. & 2 sx flocele. Heavy mud between all  
plugs. Pump cement down drill pipe. Elevation 3097 Anhydrite 2611-37',  
Arbuckle -none present. Top Dakota 1550-1547"

Plugging Proposal Received by Dale Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X X

Operations Completed: Hour: 3:45 am Day: 27 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug @ 2630' w/ 25 sx  
2nd plug @ 1850' w/ 100 sx.  
3rd plug @ 330' w/ 40 sx.  
4th plug @ 40' w/ 10 sx.

RECEIVED  
STATE CORPORATION COMMISSION  
7-6-88  
JUL 6 1988

15 sx in water well. 15 sx in ratchole.

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Allied Cementing Co.  
(If additional description is necessary, use BACK of this form.)

INVOICED (If did not) observe this plugging.

DATE 7-8-88

INV. NO. 21236

Signed Dale F. Balthazor (TECHNICIAN)