

4-061214

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-193-20,668-0000
~~RT KCC~~
~~SE NW NW SE~~ /4 SEC. 07 , 10 S, 32 W
2010 feet from S section line
2010 feet from E section line

Operator license# 3988
Operator: Slawson Exploration Co.
Address: 200 N. Harvey #1412
Oklahoma City, OK 73102

Lease: Park College Well # 1
County: Thomas
Well total depth 4700 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 308 feet

Aband. oil well___, Gas well___, Input well___, SWD___, D & A X

Plugging contractor: Murfin Drilling Company, Inc. License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: 12:30 A.M. Day: 5 Month: December Year: 1999

Plugging proposal received from: Ed McKenna

Company: Murfin Drilling Company, Inc. Phone: -

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour 3:00 A.M. , Day: 5 , Month: December , Year: 1999

Actual plugging report: ' - 2616'.

1st. Plug at 2625' w/25 sxs cement. Anhydrite 2598' - 2628'.

2nd. Plug at 1950' w/100 sxs cement. Dakota 1481' - 1781'.

3rd. Plug at 360' w/40 sxs cement. Surface pipe to 308'.

4th. Plug at 40' w/10 sxs cement.

15 sxs in rathole.

Remarks: Allied Cementing.
Condition of casing in hole): GOOD X BAD _____ Anhy.plug: YES _____ X NO _____
Bottom plug(in place): YES _____, CALC _____, NO X Dakota plug: YES X, NO _____
Plugged through TUBING _____, CASING _____. Elevation: 3081 GL

I did[] / did not[X] observe the plugging.

INVOICED

DATE 12/22/99

WV. NO. 06/0/7

(Signature)
(agent)
RECEIVED
ST. CORPORATION COMMISSION
12-21-99
DEC 21 1999
Conservation Division
Wichita, Kansas