

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
11-20-67
MAY 26 1967

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Abercrombie Drilling, Incorporated,
Complete Address 801 Union Center, Wichita, Kansas.
Lease Name Schippers Well No. A-1
Location NE-SE-SE Sec. 22 Twp. 10 Rge. (E) (W) 28
County Sheridan Total Depth 4055'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 6:00 AM Day 18 Month 11 Year 1967

The above well was plugged as follows:

200'--7 5/8" Surface pipe, cement circulated with 135 Sx. (6 1/4" Hole).
Dakota section from 700' to 525'.

Circulated hole with heavy mud. Pulled DP to 720' and displaced 60 Sx. cement thru
DP from 720' to 420'. Pulled DP to 210' and displaced 15 Sx. cement thru DP from 210'
to 135'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 5 Sx. cement to bottom of
Cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. J. Chalk
Well Plugging Supervisor

DATE 11/21/67
INV. NO. 6712-W