

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address Victoria, Kansas.

Lease Name Schippers Well No. 1

Location NE SW NE 440'W & 440'S of CNE Sec. 22 Twp. 10 Rge. (E) (W) 28

County Sheridan Total Depth 4100'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leo J. Dreiling & Sons, Incorporated,

Address Victoria, Kansas. License No.

Operation Completed: Hour 3:45 AM Day 9 Month 4 Year 1968

The above well was plugged as follows:

213'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Top of Dakota Section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 100 Sx. cement thru
DP from 1275' to 950'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 4/11/68
INV. NO. 9590-W