

15-179-20180-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company & Nadel and Gussman,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name Chapman Well No. 1

Location SW-SW-NW Sec. 9 Twp. 10 Rge. (E) (W) 28

County Sheridan Total Depth 4165'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Murfin Drilling Company,

Address: 617 Union Center Building, Wichita, Kansas. License No. _____

Operation Completed: Hour 6:00PM Day 3 Month 2 Year 1969

The Above well was plugged as follows:

274'--8 5/8" Surface casing cement circulated with 200 Sx.
Top of Dakota section @ 1250'.

Circulated hole with heavy mud. Pulled DP to 1480' and displaced 100 Sx. cement thru
DP from 1480' to 1100'. Pulled DP to 280' and displaced 20 Sx. cement thru DP from
280' to 220'. Pulled DP, set bridge @ 20' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. D. Nichols
Well Plugging Supervisor

INVOICED

DATE 2/6/69
INV. NO. 9289-W