

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 2 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Murfin-Kantor & Executive,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Jarvis Well No. 1

Location CNW-SW Sec. 26 Twp. 10 Rge. (E) (W) 29

County Sheridan Total Depth 3859'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita, Kans. License No.

Operation Completed: Hour 7:00 PM Day 27 Month 5 Year 1970

The above well was plugged as follows:

253'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1100'.

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 100-Sx. cement thru
DP from 1325' to 1000'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Dickals
Well Plugging Supervisor

DATE 6/2/70
INV. NO. 1983-W