

15-179-20264-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 2 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mallonee-Mahoney, Incorporated,

Complete Address 925 Sutton Place, Wichita, Kansas.

Lease Name Broeckelman Well No. 1

Location CSW-SW Sec. 6 Twp. 10 Rge. (E) (W) 30

County Sheridan Total Depth 4655'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Shields Drilling Company, Incorporated,

Address Shields Building, Russell, Kansas. License No.

Operation Completed: Hour 3:00 PM Day 29 Month 8 Year 1970

The above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1375'.

Circulated hole with heavy mud. Pulled DP to 1600' and displaced 100 Sx. cement thru
DP from 1600' to 1275'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/2/70
INV. NO. 2473-W

Signed: W. L. Nichols
Well Plugging Supervisor