

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 17 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Shields Oil Producers, Incorporated,

Complete Address Shields Building, Russell, Kansas.

Lease Name Baalman Well No. A-1

Location NW-NW-SW Sec. 1 Twp. 10 Rge. (E) (W) 30

County Sheridan Total Depth 4266'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Shields Drilling Company, Incorporated,

Address Shields Bldg., Russell, Kansas. License No.       

Operation Completed: Hour 3:30 PM Day 7 Month 8 Year 1970

The above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 170 Sx.  
Top of Dakota section @ 1325'.

Circulated hole with heavy mud. Pulled DP to 1550' and displaced 100 Sx. cement thru  
DP from 1550' to 1225'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from  
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/10/70 - correction

INV. NO. 2353-W

Signed: M. L. Nichols  
Well Plugging Supervisor