

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
11-29-67
NOV 29 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Sun Oil Company,

Complete Address Box #3383, Tulsa, Oklahoma.

Lease Name Project Well No. 3

Location SE/4 of Sec. 31 Twp. 10 Rge. (E) (W) 29

County Sheridan Total Depth 2029'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated STRATOGRAPHIC TEST.

Plugging Contractor Abercrombie Drilling, Incorporated,

Address 801 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 7:00PM Day 26 Month 11 Year 1967

The above well was plugged as follows:

319'--7" OD Surface pipe, cement circulated with 120 Sx. (6 1/4" Hole).
Dakota section from 1245' to 1550'.

Circulated hole with heavy mud. Pulled DP to 1575' and displaced 85 Sx. cement thru
DP from 1575' to 1150'. Pulled DP to 330' and displaced 20 Sx. cement thru DP from
330' to 230'. Pulled DP, set bridge @ 30' with 1/2 sack hulls and 5 Sx. cement to
bottom of cellar. Used 5 Sx. cement in rat hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Nichols
Well Plugging Supervisor

DATE 11-29-67

INV. NO. 6796-W