

KANSAS

*AL*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 27 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Comet Petroleum Corporation, -

Complete Address 200 West Douglas, Suite 500, Wichita, Kansas.

Lease Name Broeckelman Well No. 1

Location CNE-SW Sec. 6 Twp. 10 Rge. (E) (W) 30

County Sheridan Total Depth 4659'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.     

Operation Completed: Hour 10:30 PM Day 24 Month 9 Year 1971

The above well was plugged as follows:

238'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1325'.

Circulated hole with heavy mud. Pulled DP to 1600' and displaced 100 Sx. cement thru  
DP from 1600' to 1275'. Pulled DP to 310' and displaced 20 Sx. cement thru DP from  
310' to 250'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. L. Nichols*  
Well Plugging Supervisor

DATE 9-29-71

INV. NO. 4387-10