

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED  
FEB 12 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name John O. Farmer, Incorporated,

Complete Address Box #352, Russell, Kansas.

Lease Name Fellhoelter Well No. 1

Location CSW-NE Sec. 34 Twp. 10 Rge. (E) (W) 31

County Thomas Total Depth 4658'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 9:30 AM Day 8 Month 2 Year 1973

The above well was plugged as follows:

215'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1575' and displaced 110 Cu. Ft. cement  
thru DP from 1575' to 1250'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru  
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Diehl  
Well Plugging Supervisor

DATE 2/12/73  
INV. NO. 6968-W