

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Gore Oil Company  
Address: P.O. Box 2757, Wichita, KS 67201-2757  
Phone: (316) 263-3535 Operator License #: 5552  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 11-11-08 (Date)  
by: Marvin Mills (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
L-KC Depth to Top: 3446 Bottom: 3456 T.D. 3590'  
L-KC Depth to Top: 3470 Bottom: 3496 T.D. 3590'  
L-KC Depth to Top: 3510 Bottom: 3532 T.D. 3590'

API Number: 15-163-30203-00-00  
Lease Name: Kleinschmidt "B"  
Well Number: 6  
Spot Location (QQQQ): SE - NW - SE  
1650 Feet from  North /  South Section Line  
1650 Feet from  East /  West Section Line  
Sec. 7 Twp. 10 S. R. 17  East  West  
County: Rooks  
Date Well Completed: 8-27-66  
Plugging Commenced: 11-12-08  
Plugging Completed: 11-12-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Oil, Water	0'	153'	8 5/8"	153'	0'
Production	Oil, Water	0'	3588'	4"	3588'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Back off tbg @ 2538'. Pull tb out of hole, 78 jts. 2 3/8". Perf 2 holes @ 1800', 1480' & 840'. Run open end tbg back to 2445'. Hook up to tbg @ 2445' & pump 80 sx 60/40 4% gel & 300# hulls, 21 bbls of cmt hole circ while pumping cmt. Pull tbg to 1220' & pump 80 sx cmt w/200# hulls, cmt circ to surface. Pull tbg out of hole. Hook up to 4" casing & pump 50 sx cement, max psi 500, SI w/200 psi. Hook up to 4" & pump 40 sx cmt. SI csg w/150 psi. Allied hooked up to 8 5/8" & press to 250 holding. Topped 4" csg off w/40 sx 60/40 4% gel. Job complete

Name of Plugging Contractor: Marvin Drilling Co. Inc. License #: 30606 RECEIVED  
Address: P.O. Box 31, Russell, KS 67665-0031 KCC Pkt Per CP2/3 KANSAS CORPORATION COMMISSION  
NOV 20 2008

Name of Party Responsible for Plugging Fees: Gore Oil Company CONSERVATION DIVISION  
State of Kansas County, Sedgwick, ss. WICHITA, KS

Larry M. Jack (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry M. Jack  
(Address) Wichita, KS



RECEIVED and SWORN TO before me this 18th day of November, 20 08  
Rebecca K. Crawford My Commission Expires: 3-20-11  
Notary Public

PPT