

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Pratt Well Service, Inc.
Address: PO Box 907 Pratt, Kansas 67124
Phone: (620) 672-9571 ext 5 Operator License #: 5893
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11-12-2008 (Date)
by: Eric (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Kinderhook Sand Depth to Top: 4440 Bottom: 4460 T.D. 4484

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-047-21107-00-00
Lease Name: Gibson
Well Number: 2-A
Spot Location (QQQQ): C - W/2 - SE - NE **PKT**
1980 Feet from North / South Section Line **KCC**
980 Feet from East / West Section Line **Co PSD**
Sec. 34 Twp. 25 S. R. 16 East West
County: Edwards
Date Well Completed: 10-08-1983
Plugging Commenced: 11-12-2008
Plugging Completed: 11-14-2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
			425'	8 5/8"		
			4483'	4 1/2"		


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded back to 4260'. Capped with 4 sacks cement. Pulled 1320' of casing. Ran 34 joints tubing to 1079', broke circulation pumped 12 sacks gel and 50 sacks cement. Pulled tubing to 472' pumped 50 sacks cement, came up to 42' pumped 15 sacks of cement - Had cement to surface.

Name of Plugging Contractor: Pratt Well Service, Inc. License #: 5893 **RECEIVED**
Address: PO Box 907 Pratt, Kansas 67124 **KANSAS CORPORATION COMMISSION**
Name of Party Responsible for Plugging Fees: Pratt Well Service, Inc. **NOV 20 2008**
State of Kansas County, Pratt ss. **CONSERVATION DIVISION**

Kenneth C. Gates, President
(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Kenneth C. Gates
(Address) PO Box 907 Pratt KS 67124



SUBSCRIBED and SWORN TO before me this 19th day of November, 20 08
Janis S. Parsons My Commission Expires: 10-01-2011
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202