

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

083-20911-00-00

Lease Operator: H & C Oil Operating, Inc.  
 Address: P.O. Box 86 Plainville, KS 67663  
 Phone: (785) 434-7434 Operator License #: 8914  
 Type of Well: Oil Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: 8-29-08 (Date)  
 by: Richard Lacey Dist. #1 (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
Mississippi Depth to Top: 4639 Bottom: 4640 T.D. 4643  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-08-320911  
 Lease Name: Virginia Gleason  
 Well Number: 5  
 Spot Location (QQQQ): NW - SE - NE - SW  
SW  
1648 Feet from  North /  South Section Line  
2289 Feet from  East /  West Section Line  
 Sec. 5 Twp. 24 S. R. 21  East  West  
 County: Hodgeman  
 Date Well Completed: 11-81  
 Plugging Commenced: 11-5-08  
 Plugging Completed: 11-5-08

KCCPCT  
per  
OPS.

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put in	Pulled Out
		Surface	605'	8 5/8"	605'	None
		Surface	4639'	4 1/2"	4639'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 2700'. Set CIBP @ 650'. Perforate casing @ 630' with 4 holes. Run tubing to 600'. Circulate 55 sacks of cement to surface. Pull tubing. Pump down. 4 1/2" casing with 110 sacks. Circulate Annulus with 110 sacks. Shut in. Used 165 sacks 60/40 posmix cement with 4% gel. Cemented by allied cementing.

Name of Plugging Contractor: H2 Plains LLC License #: 33645  
 Address: P.O. Box 346 Ness City, Kansas 67560

Name of Party Responsible for Plugging Fees: H & C Oil Operating, Inc.  
 State of Kansas County, Rooks, ss.

CHARLES R RAMSAY (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the



(Signature) Charles R Ramsay  
 (Address) P.O. Box 86 Plainville, KS 67663

SUBSCRIBED and SWORN TO before me this 2nd day of December, 2008  
Irene Fellhoelter My Commission Expires: April 4, 2011  
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCCPCT  
RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 03 2008  
CONSERVATION DIVISION  
WICHITA, KS

915

# ALLIED CEMENTING CO., LLC.

32236

ATTN TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Russell

DATE <u>11-5-08</u>	SEC. <u>5</u>	TWP. <u>24</u>	RANGE <u>21</u>	CALLED OUT	ON LOCATION	JOB START <u>NOON</u>	JOB FINISH <u>1:00 PM</u>
LEASE <u>Virginia Gleason</u>	WELL # <u>S</u>	LOCATION <u>Offsite 4 W 7 N 2 E</u>			COUNTY <u>Hodgeman</u>	STATE <u>Ks</u>	

OLD OR NEW (Circle one) OLD

CONTRACTOR Plains

TYPE OF JOB Plug

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE 4 1/2 DEPTH \_\_\_\_\_

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

**EQUIPMENT**

PUMP TRUCK # 398 CEMENTER Bill HELPER Bob

BULK TRUCK # 396 DRIVER Neil

BULK TRUCK # \_\_\_\_\_ DRIVER \_\_\_\_\_

**REMARKS:**

Part - C 650  
Run Tubing to 601 Circ Cement 550ft  
to SURFACE, pull Tubing, pump down  
4 1/2 up 110 lb Circ out Ann  
with each Shut In

OWNER \_\_\_\_\_

CEMENT AMOUNT ORDERED \_\_\_\_\_

225 60/100 - 4% Gel  
Used 165 lb

COMMON	<u>99</u>	@	<u>13.50</u>	<u>1,336.50</u>
POZMIX	<u>66</u>	@	<u>7.55</u>	<u>498.30</u>
GEL	<u>5</u>	@	<u>20.25</u>	<u>101.25</u>
CHLORIDE		@		
ASC		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>232</u>	@	<u>2.25</u>	<u>522.00</u>
MILEAGE	<u>110.5</u>			<u>812.00</u>
				TOTAL <u>3,270.05</u>

**SERVICE**

DEPTH OF JOB \_\_\_\_\_

PUMP TRUCK CHARGE \_\_\_\_\_ 875.00

EXTRA FOOTAGE @ \_\_\_\_\_

MILEAGE 3.5 @ 700 245.00

MANIFOLD @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL 1120.00

CHARGE TO: H9C OP.

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

RECEIVED PLUG & FLOAT EQUIPMENT

KANSAS CORPORATION COMMISSION

DEC 03 2008

CONSERVATION DIVISION WICHITA, KS

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

To Allied Cementing Co., LLC.  
You are hereby requested to rent cementing equipment